# Probability

MATH 356 · Scribed Course Notes · Module 1

Definitions
Examples
Results
Notes

# Contents

**1 Introduction** **1**

**2 Probability Spaces** **2**
2.1 Uniform Sampling from a Finite Set . . . 2
2.2 Infinite Probability Spaces . . . 3
2.3 Uncountable Probability Spaces . . . 4

**3 Consequences of the Axioms** **4**
3.1 Set-Theoretic Notation vs. Probability . . . 4
3.2 Complements, Partitions, and Inclusion–Exclusion . . . 5
3.3 Continuity of Probability . . . 7

**4 Random Variables** **7**

**5 Conditioning** **8**
5.1 Conditional Probability and the Multiplication Rule . . . 8
5.2 Law of Total Probability and Bayes' Formula . . . 9

**6 Independence** **10**
6.1 Independent Events . . . 10
6.2 Independent Random Variables . . . 11
6.3 Conditional Independence of Events . . . 13

**7 Probability Distributions** **14**
7.1 Repeated Trials: Bernoulli and Binomial Distributions . . . 14
7.2 Product Spaces and Infinitely Many Trials . . . 15
7.3 Geometric and Negative Binomial Distributions . . . 16
7.4 The Birthday Problem and the Rayleigh Distribution . . . 16
7.5 Hypergeometric Distribution . . . 17

**8 Density and Distribution Functions** **17**
8.1 Probability Density Functions . . . 17
8.2 Examples of Continuous Random Variables . . . 18
8.3 General Random Variables . . . 19
8.4 Connection between cdf and pdf . . . 21
8.5 Connection between cdf and pmf . . . 21

**9 Expectations** **22**
9.1 Change of Variables . . . 24
9.2 Moments . . . 26
9.3 Medians and Quantiles . . . 27
9.4 Variance . . . 27

**10 The Normal / Gaussian Distribution** **29**

**11 Selected Problems and Tricks** **32**
11.1 Hidden Conditioning: the Twins Problem . . . 32
11.2 The $k$-Selection Problem . . . 32
11.3 Von Neumann's Trick: a Fair Coin from a Biased One . . . 33
11.4 The Indicator Trick . . . 34
11.5 A Biased Coin from a Fair One: Binary Expansions . . . 34
11.6 The Tail-Sum Formula . . . 35
11.7 First-Step Analysis . . . 36
11.8 Parity via Generating Functions . . . 36

# 1 Introduction

Source manuscript page 1

Professor: Louigi Addario-Berry
Scribe: Yitian Zhang

Note 1. The abbreviations used in the manuscript have been expanded in this edition; $AB := A \cap B$, $[n] := \{1, \dots, n\}$ and $(n)_k := n(n-1)\cdots(n-k+1)$ are kept.
Note 2. Red ink in the manuscript (questions, stars) is reproduced in red; blue marginal notes in blue.
Note 3. The handwritten diagrams of the manuscript are redrawn in TikZ; curves that the manuscript only sketches are plotted exactly.
Note 4. Slips of the manuscript are corrected in the text, without comment.

Let us consider the following scenarios.

**Example (Roll a fair die)**

The face $D$ that shows is a *random variable*.

$$\underbrace{\mathbb{P}}_{\text{probability}}\ (\underbrace{D=2}_{\text{event}}) = \tfrac{1}{6}, \qquad \mathbb{P}(D=k) = \tfrac{1}{6}, \quad k = 1, 2, \dots, 6.$$

□

**Example (Roll a fair die twice)**

Faces that show $= D_1, D_2$.

$$\mathbb{P}(D_1 = 2,\ D_2 = 3) = \tfrac{1}{6}\cdot\tfrac{1}{6} = \tfrac{1}{36}, \qquad \mathbb{P}(D_1 = k,\ D_2 = j) = \tfrac{1}{6}\cdot\tfrac{1}{6} = \tfrac{1}{36}, \quad j, k = 1, \dots, 6.$$

□

**Example (Choose one of two biased dice at random, roll twice)**

$$\text{Biased 1: } \begin{cases} 4,5,6 \to \mathbb{P} = \frac{2}{9} \\ 1,2,3 \to \mathbb{P} = \frac{1}{9} \end{cases} \qquad \text{Biased 2: } \begin{cases} 1,2,3 \to \mathbb{P} = \frac{2}{9} \\ 4,5,6 \to \mathbb{P} = \frac{1}{9} \end{cases}$$

$$\begin{aligned} \mathbb{P}(D_1 = 4) &= \tfrac{1}{2}\cdot\tfrac{2}{9} + \tfrac{1}{2}\cdot\tfrac{1}{9} = \tfrac{1}{6}, \\ \mathbb{P}(D_2 = 1) &= \tfrac{1}{2}\cdot\tfrac{1}{9} + \tfrac{1}{2}\cdot\tfrac{2}{9} = \tfrac{1}{6}, \\ \mathbb{P}(D_1 = 1,\ D_2 = 1) &= \tfrac{1}{2}\cdot\tfrac{1}{9}\cdot\tfrac{1}{9} + \tfrac{1}{2}\cdot\tfrac{2}{9}\cdot\tfrac{2}{9} = \tfrac{5}{162}. \end{aligned}$$

The first summand is $\mathbb{P}(\text{chose large die}) \cdot \mathbb{P}(D_1 = 1, D_2 = 1 \mid \text{chose large die})$, where "|" is read "given".

□

Q. What are events? What is independence? What are random variables? How can we model the outcome of an experiment mathematically? How do we do computations with random variables? What are conditional probabilities? What are means / expectations / moments? How do sums of random variables behave? What is universality?

Source manuscript page 2

# 2 Probability Spaces

**Definition**

A *probability space* is a triple $(\Omega, \mathcal{F}, \mathbb{P})$:

- $\Omega$ is the *sample space*;
- $\mathcal{F}$ is a set of subsets of $\Omega$, here $\mathcal{F} = 2^\Omega = \mathcal{P}(\Omega)$; elements of $\mathcal{F}$ are called *events*;
- $\mathbb{P}$ is a *probability measure*, i.e. it satisfies *Kolmogorov's axioms*:
  - (i) $\forall E \in \mathcal{F},\ 0 \le \mathbb{P}(E) \le 1$;
  - (ii) $\mathbb{P}(\emptyset) = 0,\ \mathbb{P}(\Omega) = 1$;
  - (iii) for any disjoint events $(E_i)_{i\in\mathbb{N}}$, $\mathbb{P}\Big(\bigsqcup_{i=1}^{\infty} E_i\Big) = \sum_{i=1}^{\infty} \mathbb{P}(E_i)$ (countable additivity).

□

Source manuscript page 3

Exercise. Does (i) follow from (ii) and (iii)?

**Example (Roll a fair die once)**

$\Omega = \{1, 2, \dots, 6\}$, $\mathcal{F} = 2^\Omega$ = all subsets of $\Omega$, $\mathbb{P}(E) = |E|/6$. For instance $\mathbb{P}(\{1, 3, 5\}) = 3/6 = 1/2$. □

**Example (Roll a fair die twice)**

Let $[6] := \{1, 2, \dots, 6\}$. Then $\Omega = [6] \times [6]$, $\mathcal{F} = 2^\Omega$, $\mathbb{P}(E) = |E|/36$. □

## 2.1 Uniform Sampling from a Finite Set

**Example (Sampling from $[50] = \{1, \dots, 50\}$)**

Say the sample is 7, 12, 43. Questions to think of: with or without replacement? Does the order matter? The answers change the sample space, and with it the probability of the observed sample:

| | $\Omega$ | $\mathbb{P}((7, 12, 43))$ |
|---|---|---|
| with replacement, order matters | $\{(a, b, c)\}$ | $\frac{1}{\lvert\Omega\rvert} = \frac{1}{50^3}$ |
| w/o replacement, order matters | $\{(a, b, c) :\ a, b, c \text{ distinct}\}$ | $\frac{1}{50 \cdot 49 \cdot 48} = \frac{1}{(50)_3}$ |
| w/o replacement, order does not matter | $\{S \subseteq [50] :\ \#S = 3\}$ | $\mathbb{P}(\{7, 12, 43\}) = \frac{1}{\binom{50}{3}} = \frac{3!}{(50)_3}$ |
| with replacement, order irrelevant | $\{\{a_1, a_2, a_3\} :\ a_i \in [50]\}$ | $\frac{6}{50^3}$ |

□

Source manuscript page 4

**Example (Lotto 6/49)**

The probability that the draw has 3 odd and 3 even numbers, computed two ways, in two different sample spaces.

First way: order matters. $\Omega = \{(a,b,c,d,e,f) : \ a,b,\dots,f \in [49] \text{ distinct}\}$, $\mathbb{P}$ = uniform probability measure on $\Omega$, i.e. $\mathbb{P}(E) = |E|/|\Omega|$ for all $E \in \mathcal{F}$. For one fixed pattern, count the tuples that fit it ([49] has 25 odd and 24 even numbers) and divide by $|\Omega| = (49)_6$:

$$\mathbb{P}\big((\text{odd},\text{even},\text{odd},\dots,\text{odd},\text{even})\big) = \frac{(25)_3\,(24)_3}{(49)_6}.$$

Every pattern with 3 odd positions has this same probability, and the patterns are disjoint, so

$$\mathbb{P}(3 \text{ odds, } 3 \text{ evens}) = \underbrace{\binom{6}{3}}_{\text{choosing the odd positions}} \frac{(25)_3\,(24)_3}{(49)_6}.$$

Second way: order does not matter. In a different sample space, $\Omega' = \{S \subseteq [49] : \ \#S = 6\}$ with its uniform probability measure $\mathbb{P}'$, count the sets with 3 odd and 3 even numbers and divide by $|\Omega'| = \binom{49}{6}$:

$$\mathbb{P}'(3 \text{ odds, } 3 \text{ evens}) = \frac{\binom{25}{3}\binom{24}{3}}{\binom{49}{6}}.$$

The two answers agree. Since $(n)_k = k!\binom{n}{k}$,

$$\underbrace{\binom{6}{3}\frac{(25)_3\,(24)_3}{(49)_6}}_{\text{first way, in } \Omega} = \frac{6!}{3!\,3!}\cdot\frac{3!\binom{25}{3}\cdot 3!\binom{24}{3}}{6!\binom{49}{6}} = \underbrace{\frac{\binom{25}{3}\binom{24}{3}}{\binom{49}{6}}}_{\text{second way, in } \Omega'}.$$

□

**Remark**

Although the counts are different (the first way of computation takes order into consideration, while the second way only chooses), by putting them in their own respective $\Omega$ they give rise to the same probability of getting 3 evens and 3 odds. □

## 2.2 Infinite Probability Spaces

Source manuscript page 5

**Example (Toss a coin repeatedly, count the number of tails before the first head)**

$\Omega = \{0,1,\dots\}$, $\mathcal{F} = 2^\Omega$.

- Fair coin: $\mathbb{P}(\{k\}) = \mathbb{P}(k \text{ tails before a head}) = \frac{1}{2^k}\cdot\frac{1}{2} = \frac{1}{2^{k+1}}$.
- $p$-biased coin (probability of head $= p$): $\mathbb{P}(\{k\}) = (1-p)^k\,p$.

Sometimes we refer to this as Geom($p$), a *geometric distribution.* □

## 2.3 Uncountable Probability Spaces

**Example (Throw a dart at a uniformly random location on a dart board)**

$$\Omega = B(0,1) = \{(x,y) \in \mathbb{R}^2 \mid x^2 + y^2 \le 1\}, \qquad \mathbb{P}(R) := \frac{\text{Area}(R)}{\text{Area}(B(0,1))} \quad \text{for } R \subseteq \Omega.$$

□

**Remark**

This definition is heuristic. It relies on the measurability of the set $R$, and the justification of the third of Kolmogorov's axioms relies on the fact that Lebesgue measure satisfies countable additivity. □

**Claim**

For any point $p \in \Omega$, $\mathbb{P}(\{p\}) = 0$.

Source manuscript page 6

*Proof.* For any $p \in B(0,1)$, fix $\varepsilon$ small; then $\mathbb{P}(B(p,\varepsilon)) = \dfrac{\pi\varepsilon^2}{\pi} = \varepsilon^2$ and $\{p\} \subseteq B(p,\varepsilon) \subseteq B(0,1)$. Thus $\mathbb{P}(\{p\}) \le \varepsilon^2$. Send $\varepsilon \to 0$: $\mathbb{P}(\{p\}) = 0$. □

We used the fact: if $A \subseteq B$, then

$$\mathbb{P}(B) = \mathbb{P}\big(A \cup (B \setminus A)\big) = \mathbb{P}(A) + \mathbb{P}(B \setminus A) \ge \mathbb{P}(A).$$

**Remark**


$$\mathbb{P}\Big(\bigcup_{p \in B(0,\frac{1}{2})} \{p\}\Big) = \mathbb{P}\big(B(0,\tfrac{1}{2})\big) = \tfrac{1}{4} \neq \sum_{p \in B(0,\frac{1}{2})} \mathbb{P}(\{p\}) = 0.$$

This is because we are looking at an uncountably infinite sum. □

# 3 Consequences of the Axioms

## 3.1 Set-Theoretic Notation vs. Probability

$$\mathbb{P}(A) + \mathbb{P}(A^c) = \mathbb{P}(\Omega) = 1, \quad AB := A \cap B, \quad AB^c = A \setminus B, \quad BA^c = B \setminus A, \quad (AB)^c = A^c \cup B^c.$$




For a sequence of events $E_1, \dots, E_n$,

$$\begin{aligned}\mathbb{P}(E_1 \cup E_2 \cup \cdots \cup E_n) &= \mathbb{P}\big(E_1 \cup (E_1^c E_2) \cup \cdots \cup (E_1^c E_2^c \cdots E_{n-1}^c E_n)\big) \\ &= \mathbb{P}(E_1) + \mathbb{P}(E_1^c E_2) + \cdots + \mathbb{P}(E_1^c \cdots E_{n-1}^c E_n) \\ &\le \mathbb{P}(E_1) + \cdots + \mathbb{P}(E_n).\end{aligned}$$

Source manuscript page 7

Called *subadditivity*.

Principle. To find $\mathbb{P}$ of a complicated event, compute simpler disjoint sub-events, then add up.

**Example (Dice game)**

Players $A, B$ take turns rolling a fair die, $A$ first. $A$ wins on $\{1,2\}$; $B$ wins on $\{3,4,5,6\}$. Let $A_k = \{A \text{ wins on her } k\text{th roll}\}$.
Want: $\mathbb{P}(A \text{ rolls} \le 4 \text{ times and wins})$. Then $E = A_1 \cup A_2 \cup A_3 \cup A_4$, and

$$\begin{array}{c|cccccccc} A_k: & a_1 & b_1 & a_2 & b_2 & \cdots & a_{k-1} & b_{k-1} & a_k \\ \hline \mathbb{P}: & \frac{2}{3} & \frac{1}{3} & \frac{2}{3} & \frac{1}{3} & \cdots & \frac{2}{3} & \frac{1}{3} & \frac{1}{3} \end{array} \qquad \Longrightarrow \qquad \mathbb{P}(A_k) = \left(\frac{2}{9}\right)^{k-1}\frac{1}{3}.$$

Thus $\mathbb{P}(E) = \mathbb{P}(A_1) + \mathbb{P}(A_2) + \mathbb{P}(A_3) + \mathbb{P}(A_4)$, and

$$\mathbb{P}(A \text{ wins}) = \sum_{k=1}^{\infty} \mathbb{P}(A_k) = \sum_{k=1}^{\infty} \left(\frac{2}{9}\right)^{k-1}\frac{1}{3} = \frac{3}{7}.$$


□

Source manuscript page 8

## 3.2 Complements, Partitions, and Inclusion–Exclusion

**Proposition**

(a) $\forall A \in \mathcal{F}$, $\mathbb{P}(A) + \mathbb{P}(A^c) = 1$.
(b) $\forall A, B \in \mathcal{F}$, $\mathbb{P}(A) = \mathbb{P}(A \cap B) + \mathbb{P}(A \cap B^c)$.




Aside on notation.

$$\sum_{i=1}^{n} a_i = \sum_{i \in [n]} a_i, \qquad \sum_{1 \le i < j \le n} a_{\{i,j\}} = \sum_{\{i,j\} \subseteq [n]} a_{\{i,j\}}, \quad a_{ij} = a_{ji} = a_{\{i,j\}},$$

$$\sum_{1 \le i < j < k \le n} a_{\{i,j,k\}} = \sum_{\{i,j,k\} \subseteq [n]} a_{\{i,j,k\}} = \sum_{\substack{S \subseteq [n] \\ |S| = 3}} a_S.$$

These give a more compact way of writing the sum.

**Proposition (Inclusion–Exclusion)**

For events $E_1, \dots, E_n \subseteq \Omega$,

$$\mathbb{P}\Big(\bigcup_{i\in[n]} E_i\Big) = \sum_{k=1}^{n} (-1)^{k+1} \sum_{\substack{S\subseteq[n]\\|S|=k}} \mathbb{P}\Big(\bigcap_{i\in S} E_i\Big). \tag{$*$}$$

**Example**

$\mathbb{P}(A\cup B\cup C) = \mathbb{P}(A)+\mathbb{P}(B)+\mathbb{P}(C)-\mathbb{P}(AB)-\mathbb{P}(BC)-\mathbb{P}(AC)+\mathbb{P}(ABC)$. □

*Proof of* $(*)$. $n=1$, $n=2$ done (geometrically obvious). Suppose the equation holds for $\le n$. We proceed by strong induction. Let $E_1, \dots, E_{n+1} \subseteq \Omega$, $A = E_1 \cup \cdots \cup E_n$, $B = E_{n+1}$. Then

Source manuscript page 9

$$\mathbb{P}(A) = \sum_{k=1}^{n} (-1)^{k+1} \sum_{\substack{S\subseteq[n]\\|S|=k}} \mathbb{P}\Big(\bigcap_{i\in S} E_i\Big), \qquad \mathbb{P}(B) = \mathbb{P}(E_{n+1}),$$

$$\mathbb{P}(A\cap B) = \mathbb{P}\big((E_1\cap E_{n+1})\cup\cdots\cup(E_n\cap E_{n+1})\big) = \sum_{k=1}^{n} (-1)^{k+1} \sum_{\substack{S\subseteq[n]\\|S|=k}} \mathbb{P}\Big(\bigcap_{i\in S} (E_i\cap E_{n+1})\Big).$$

Consider the sum $\mathbb{P}(A\cup B) = \mathbb{P}(A)+\mathbb{P}(B)-\mathbb{P}(A\cap B)$ in cases, comparing the terms with those in $(*)$:

1. if the intersection does not contain $E_{n+1}$, the term appears in $\mathbb{P}(A)$;
2. if the intersection contains $E_{n+1}$ as the only event, the term is $\mathbb{P}(B)$;
3. if the intersection contains $E_{n+1}$ and other events, the term appears in $\mathbb{P}(A\cap B)$, with sign fixed by "$-\mathbb{P}(A\cap B)$" and a shift of index.

Thus $\mathbb{P}(A\cup B)$ = LHS of $(*)$ = RHS of $(*)$. [By "intersection" we mean a term in the RHS of $(*)$.] □

**Example (Hats)**

$n$ individuals, $n$ hats. Each individual chooses a hat uniformly at random. What is $\mathbb{P}$(at least one person gets their own hat)?

Source manuscript page 10

Let $E_i := \{\text{person } i \text{ gets their own hat}\}$. Then

$$\mathbb{P}\Big(\bigcup_{i\in[n]} E_i\Big) = \sum_{k\in[n]} (-1)^{k+1} \sum_{\substack{S\subseteq[n]\\|S|=k}} \mathbb{P}\Big(\bigcap_{i\in S} E_i\Big).$$

Furthermore, for a set $\{i_1, \dots, i_k\} \subseteq [n]$, what is $\mathbb{P}(E_{i_1}\cap\cdots\cap E_{i_k})$? Answer: $\dfrac{(n-k)!}{n!}$. Thus

$$\mathbb{P}\Big(\bigcup_{i\in[n]} E_i\Big) = \sum_{k\in[n]} (-1)^{k+1} \sum_{\substack{S\subseteq[n]\\|S|=k}} \frac{(n-k)!}{n!} = \sum_{k\in[n]} (-1)^{k+1} \binom{n}{k} \frac{(n-k)!}{n!}$$

$$= \sum_{k=1}^{n} (-1)^{k+1} \frac{n!}{k!\,(n-k)!} \cdot \frac{(n-k)!}{n!} = -\sum_{k=0}^{n} \frac{(-1)^k}{k!} + 1 \approx 1 - e^{-1}.$$

□

### 3.3 Continuity of Probability

Reading. Continuity of probability (§1.6). If $A_1 \subseteq A_2 \subseteq \cdots$, then

$$\mathbb{P}\Big(\bigcup_{n\in\mathbb{N}} A_n\Big) = \lim_{n\to\infty} \mathbb{P}(A_n).$$

## 4 Random Variables

**Definition**

A *random variable* is a function $X : \Omega \to \mathbb{R}$ for some probability space $(\Omega, \mathcal{F}, \mathbb{P})$. □

Source manuscript page 11

**Example**

$\Omega = [6]^2$ (two fair die rolls), $X((i,j)) :=$ sum of the two values.

$$\mathbb{P}(X=4) = \mathbb{P}\big(\{(i,j)\in\Omega:\ X((i,j))=4\}\big) = \mathbb{P}\big(\{(i,j)\in[6]^2:\ i+j=4\}\big) = \frac{3}{36} = \frac{1}{12}.$$

□

**Example**

$\Omega = [6]^{10}$ models rolling a fair die 10 times. $X(\omega) :=$ number of times a 1 is rolled. Then $\mathbb{P}(X=4) = \frac{1}{6^{10}}\binom{10}{4}5^6$. □

Notation. When we say $X \in B$, that means $\text{Range}(X) \subseteq B \subseteq \mathbb{R}$.

**Definition**

The *distribution* of a random variable $X$ is the collection of probabilities $\mathbb{P}(X \in B)$, $B \subseteq \mathbb{R}$. We may think of this as a function

$$2^{\mathbb{R}} \longrightarrow [0,1], \qquad B \longmapsto \mathbb{P}(X \in B).$$

□

**Remark**

1. It is in fact impossible to do so in a meaningful way, as we cannot define a measure on $2^{\mathbb{R}}$.
2. We only need $\{\mathbb{P}(X \in (-\infty, b]) :\ b \in \mathbb{R}\}$ to characterize the distribution of a random variable $X$.

□

Source manuscript page 12

**Definition**

A random variable $X$ is

- *discrete* if there exists a countable set $S$ such that $\mathbb{P}(X \in S) = 1$;

- *continuous* if there exists $f : \mathbb{R} \to [0, \infty)$ such that for all $a, b \in \mathbb{R}$, $a \leq b$,

$$\mathbb{P}(X \in [a, b]) = \int_a^b f(x)\, dx.$$

For a discrete random variable $X$ taking values in $S$, the *probability mass function* of $X$ is the function

$$f : S \longrightarrow [0, 1], \qquad s \longmapsto \mathbb{P}(X = s).$$

□

# 5 Conditioning

Fix a probability space $(\Omega, \mathcal{F}, \mathbb{P})$.


## 5.1 Conditional Probability and the Multiplication Rule

**Definition**

Given events $A, B$ with $\mathbb{P}(B) > 0$, let

$$\mathbb{P}(A \mid B) := \frac{\mathbb{P}(A \cap B)}{\mathbb{P}(B)},$$

the *conditional probability of $A$ given $B$*. □




**Example (Random sampling of 3 balls without replacement)**

Urn with 4 red, 6 purple.

$$\mathbb{P}(2 \text{ red} \mid \geq 1 \text{ red}) = \frac{\mathbb{P}\big((2 \text{ red}) \cap (\geq 1 \text{ red})\big)}{\mathbb{P}(\geq 1 \text{ red})} = \frac{\mathbb{P}(2 \text{ red})}{\mathbb{P}(\geq 1 \text{ red})} = \frac{?/720}{?/720}.$$

Source manuscript page 13

$$\mathbb{P}(2 \text{ red}) = \mathbb{P}(RRP) + \mathbb{P}(RPR) + \mathbb{P}(PRR) = \frac{4 \cdot 3 \cdot 6}{720} \cdot 3,$$
$$\mathbb{P}(\geq 1 \text{ red}) = 1 - \mathbb{P}(PPP) = 1 - \frac{6 \cdot 5 \cdot 4}{720} = \frac{600}{720}.$$

Thus $\mathbb{P}(A \mid B) = \dfrac{3 \cdot 72}{600} = \dfrac{9}{25}$. □

**Proposition (Multiplication rule)**

$$\mathbb{P}(AB) = \mathbb{P}(A)\,\mathbb{P}(B \mid A) = \mathbb{P}(B)\,\mathbb{P}(A \mid B).$$

More generally, if $\mathbb{P}(A_1 \cdots A_n) > 0$, then

$$\mathbb{P}(A_1 A_2 \cdots A_n) = \mathbb{P}(A_1)\,\mathbb{P}(A_2 \mid A_1)\,\mathbb{P}(A_3 \mid A_1, A_2) \cdots \mathbb{P}(A_n \mid A_1, \ldots, A_{n-1}).$$

*Proof.* Exercise. Use the definition of conditional probability and induction on $n$. □


**Example (3 draws from the urn)**

$$\mathbb{P}(RRP) = \mathbb{P}(\text{1st red}) \cdot \mathbb{P}(\text{2nd red} \mid \text{1st red}) \cdot \mathbb{P}(\text{3rd purple} \mid \text{1st red, 2nd red}) = \frac{4}{10} \cdot \frac{1}{3} \cdot \frac{3}{4} = \frac{1}{10}.$$

□

**Example (Two urns)**

Urn 1 holds $2G, 3R$ and urn 2 holds $1R, 3Y$; an urn is chosen with probability $\frac{1}{2}$ each, then a ball is drawn.




$$\mathbb{P}(\text{yellow}) = \mathbb{P}(\text{yellow} \cap \text{urn 2}) = \mathbb{P}(\text{urn 2})\,\mathbb{P}(\text{yellow} \mid \text{urn 2}) = \tfrac{3}{8}.$$

Source manuscript page 14

$$\begin{aligned}\mathbb{P}(\text{red}) &= \mathbb{P}\big(\{\text{red}, \text{urn 1}\} \sqcup \{\text{red}, \text{urn 2}\}\big) = \mathbb{P}(\text{red} \cap \text{urn 1}) + \mathbb{P}(\text{red} \cap \text{urn 2}) \\ &= \mathbb{P}(1)\,\mathbb{P}(R \mid 1) + \mathbb{P}(2)\,\mathbb{P}(R \mid 2) = \cdots = \tfrac{17}{40}.\end{aligned}$$

□

## 5.2 Law of Total Probability and Bayes' Formula

**Proposition (Law of total probability)**

If events $(B_i)_{i \in [n]}$ partition $\Omega$ with $\mathbb{P}(B_i) > 0$ for all $i \in [n]$, then for any event $A$,

$$\mathbb{P}(A) = \sum_{i \in [n]} \mathbb{P}(A \mid B_i)\,\mathbb{P}(B_i).$$

*Proof.* Exercise. □

**Proposition (Bayes' formula)**

For events $A, B$ with $\mathbb{P}(A), \mathbb{P}(B) \neq 0$,

$$\mathbb{P}(A \mid B) = \frac{\mathbb{P}(B \mid A)\,\mathbb{P}(A)}{\mathbb{P}(B)} = \frac{\mathbb{P}(B \mid A)\,\mathbb{P}(A)}{\mathbb{P}(B \mid A)\,\mathbb{P}(A) + \mathbb{P}(B \mid A^c)\,\mathbb{P}(A^c)}.$$

**Example (Base rate fallacy)**

The incidence of strep throat in the general population is $\frac{1}{200}$. The rapid strep test has false positive rate $\frac{1}{50}$ and false negative rate $\frac{1}{3}$. Test a random person; $S = \{\text{has strep}\}$, $T = \{\text{tests positive}\}$.

$$\mathbb{P}(S \mid T) = \frac{\mathbb{P}(T \mid S)\,\mathbb{P}(S)}{\mathbb{P}(T \mid S)\,\mathbb{P}(S) + \mathbb{P}(T \mid S^c)\,\mathbb{P}(S^c)} = \frac{\frac{2}{3} \cdot \frac{1}{200}}{\frac{2}{3} \cdot \frac{1}{200} + \frac{1}{50} \cdot \frac{199}{200}} \approx 0.14.$$

Source manuscript page 15

Takeaway. Even if the rapid test is reasonably accurate, whether a positive result implies a high chance of infection depends also on the base rate ($\frac{1}{200}$) of the disease. □

**Proposition (General form of Bayes' formula)**

If events $\{B_i\}_{i \in [n]}$ partition $\Omega$ and $\mathbb{P}(B_i) > 0$ for all $i$, then for all events $A, B$ with $\mathbb{P}(A), \mathbb{P}(B) > 0$,

$$\mathbb{P}(B \mid A) = \frac{\mathbb{P}(A \mid B)\,\mathbb{P}(B)}{\sum_{i \in [n]} \mathbb{P}(A \mid B_i)\,\mathbb{P}(B_i)}.$$

**Example (Three types of coins)**

Fair coin: $\mathbb{P}(\text{tails}) = \frac{1}{2}$, $\frac{9}{10}$ of coins. Slight bias: $\mathbb{P}(\text{tails}) = \frac{6}{10}$, $\frac{9}{100}$ of coins. Heavy bias: $\mathbb{P}(\text{tails}) = \frac{9}{10}$, $\frac{1}{100}$ of coins.

$$\mathbb{P}(F \mid \text{Tails}) = \frac{\mathbb{P}(\text{Tails} \mid F)\,\mathbb{P}(F)}{\mathbb{P}(\text{Tails} \mid F)\,\mathbb{P}(F) + \mathbb{P}(\text{Tails} \mid S)\,\mathbb{P}(S) + \mathbb{P}(\text{Tails} \mid H)\,\mathbb{P}(H)} = \cdots = \frac{450}{513} \approx 0.88.$$

□

# 6 Independence

Source manuscript page 16

## 6.1 Independent Events

**Definition**

Events $A, B$ are *independent* if $\mathbb{P}(A)\,\mathbb{P}(B) = \mathbb{P}(AB)$. Events $A_1, \ldots, A_n$ are *independent* if for all $I \subseteq [n]$,

$$\mathbb{P}\Big(\bigcap_{i \in I} A_i\Big) = \prod_{i \in I} \mathbb{P}(A_i).$$

□

**Example (Two coin tosses)**


$\Omega = \{T, H\}^2$ with the uniform probability measure, $(\omega_1, \omega_2) \in \Omega$. Let $A = \{\omega_1 = H\}$, $B = \{\omega_2 = H\}$, $C = \{\text{number of heads is even}\}$. Then

$$\mathbb{P}(A) = \mathbb{P}(B) = \mathbb{P}(C) = \tfrac{1}{2}, \qquad \mathbb{P}(AB) = \mathbb{P}(BC) = \mathbb{P}(AC) = \tfrac{1}{4}.$$

Yet $\mathbb{P}(ABC) = \mathbb{P}(C \mid AB)\,\mathbb{P}(AB) = 1 \cdot \frac{1}{4} = \frac{1}{4}$. Thus $\{A, B\}$, $\{B, C\}$, $\{A, C\}$ are independent events, while $\{A, B, C\}$ is not. □

**Example (Two samples from an urn)**

The urn holds 4 red and 7 green balls. $A = \{\text{1st sample red}\}$, $B = \{\text{2nd sample green}\}$.





With replacement. $\mathbb{P}(AB) = \dfrac{4 \cdot 7}{121} = \mathbb{P}(A)\,\mathbb{P}(B)$. Hence independent.

Source manuscript page 17

Without replacement. $\mathbb{P}(AB) = \dfrac{4 \cdot 7}{11 \cdot 10} = \dfrac{28}{110}$, while $\mathbb{P}(A) = \dfrac{4}{11}$, $\mathbb{P}(B) = \dfrac{7}{11}$; thus $\mathbb{P}(AB) \neq \mathbb{P}(A)\,\mathbb{P}(B)$, so $A, B$ are not independent. □

**Example (Circuit)**

Switches 1 and 2 are in series on the top branch, switch 3 alone on the bottom branch, and the two branches are in parallel between $a$ and $b$.




Let $p_i := \mathbb{P}(\text{switch } i \text{ is on})$; switch states are independent. Then

$$\begin{aligned} \mathbb{P}(\text{current can go } a \to b) &= \mathbb{P}(\text{top}) + \mathbb{P}(\text{bottom}) - \mathbb{P}(\text{both}) \qquad \text{(inclusion–exclusion)} \\ &= p_1 p_2 + p_3 - p_1 p_2 p_3 \qquad \text{by independence.} \end{aligned}$$

□

## 6.2 Independent Random Variables

Notation.

$$(x_1 + x_3 + x_5)(y_2 + y_6 + y_8)(z_3 + z_6 + z_9) = \sum_{i \in \{1,3,5\}} \sum_{j \in \{2,6,8\}} \sum_{k \in \{3,6,9\}} x_i y_j z_k = \sum_{(i,j,k) \in I \times J \times K} x_i y_j z_k,$$

with $I = \{1, 3, 5\}$, $J = \{2, 6, 8\}$, $K = \{3, 6, 9\}$.

**Definition**

Random variables $X_1, \dots, X_n : \Omega \to \mathbb{R}$ are (mutually) *independent* if for all $B_1, \dots, B_n \subseteq \mathbb{R}$,

$$\mathbb{P}(X_1 \in B_1, \dots, X_n \in B_n) = \mathbb{P}(X_1 \in B_1) \cdots \mathbb{P}(X_n \in B_n), \quad \text{i.e.} \quad \mathbb{P}\Big( \bigcap_{i \in [n]} \{X_i \in B_i\} \Big) = \prod_{i \in [n]} \mathbb{P}(X_i \in B_i).$$

□

Source manuscript page 18

Recall. A random variable $X$ is discrete if there exists a finite or countable set $S \subseteq \mathbb{R}$ such that $\mathbb{P}(X \in S) = 1$. In this case the set of *possible values* of $X$ is

$$S_X := \{x \in \mathbb{R} \mid \mathbb{P}(X = x) > 0\}.$$

**Proposition**

Discrete random variables $X_1, \dots, X_n$ are independent if and only if for all possible values $x_i$ of $X_i$,

$$\mathbb{P}(X_1 = x_1, \dots, X_n = x_n) = \prod_{i=1}^{n} \mathbb{P}(X_i = x_i).$$

*Proof.* ($\Rightarrow$) By definition.

($\Leftarrow$) Let $S_i :=$ possible values of $X_i$. Fix $B_1, \dots, B_n \subseteq \mathbb{R}$. Then


$$\mathbb{P}\Big( \bigcap_{i \in [n]} \{X_i \in B_i\} \Big) = \mathbb{P}\Big( \bigcap_{i \in [n]} \{X_i \in B_i \cap S_i\} \Big)$$

(exercise: show this equality using Kolmogorov's axioms)

$$\begin{aligned}
&= \mathbb{P}\Big( \bigcup_{x_1 \in B_1 \cap S_1} \cdots \bigcup_{x_n \in B_n \cap S_n} \{X_1 = x_1, \dots, X_n = x_n\} \Big) \\
&= \sum_{x_1 \in B_1 \cap S_1} \cdots \sum_{x_n \in B_n \cap S_n} \mathbb{P}(X_1 = x_1, \dots, X_n = x_n) \\
&= \sum_{x_1 \in B_1 \cap S_1} \cdots \sum_{x_n \in B_n \cap S_n} \prod_{i=1}^{n} \mathbb{P}(X_i = x_i) \\
&= \prod_{i=1}^{n} \Big( \sum_{x_i \in B_i \cap S_i} \mathbb{P}(X_i = x_i) \Big) = \prod_{i=1}^{n} \mathbb{P}(X_i \in B_i \cap S_i) \\
&= \prod_{i=1}^{n} \mathbb{P}(X_i \in B_i).
\end{aligned}$$

Source manuscript page 19

So the $X_i$ are independent from the definition. □



**Fact**

Continuous random variables $X_1, \dots, X_n$ are independent if and only if for all $a_1 < b_1, \dots, a_n < b_n$,

$$\mathbb{P}\big(X_1 \in (a_1, b_1), \dots, X_n \in (a_n, b_n)\big) = \prod_{i=1}^{n} \mathbb{P}\big(X_i \in (a_i, b_i)\big).$$

**Example (Sampling $k$ times from $[n]$ with replacement)**

$\Omega = [n]^k$ with the uniform probability measure. For $\omega = (\omega_1, \dots, \omega_k) \in [n]^k$ let $X_i(\omega) = \omega_i$. Then

$$\mathbb{P}(X_i = j) = \mathbb{P}(\{\omega : \ \omega_i = j\}) = \frac{n^{k-1}}{n^k} = \frac{1}{n}.$$

To check independence, compute

$$\mathbb{P}(X_1 = j_1, X_2 = j_2, \dots, X_k = j_k) = \mathbb{P}\big(\omega = (j_1, \dots, j_k)\big) = \frac{1}{n^k} = \left(\frac{1}{n}\right)^k = \prod_{i=1}^{k} \mathbb{P}(X_i = j_i).$$

□

**Example (Without replacement, previous example)**

$\Omega = \{\omega = (\omega_1, \dots, \omega_k) \in [n]^k : \ \omega_i \neq \omega_j \text{ for } i \neq j\}$ with the uniform probability measure, $X_i(\omega) = \omega_i$.

$$\mathbb{P}(X_i = j) = \frac{|\{\omega \in \Omega : \ \omega_i = j\}|}{(n)_k} = \frac{(n-1)_{k-1}}{(n)_k} = \frac{1}{n}.$$

Meanwhile,

$$\mathbb{P}(X_1 = j_1, \dots, X_k = j_k) = \begin{cases} \dfrac{1}{(n)_k}, & \text{if the } j_i \text{ are all distinct,} \\ 0, & \text{otherwise,} \end{cases} \qquad \neq \ \frac{1}{n^k}.$$

Source manuscript page 20

Hence the random variables are not independent. □

## 6.3 Conditional Independence of Events

**Definition**

Given events $A, B_1, B_2 \in \mathcal{F}$ with $\mathbb{P}(A) > 0$, we say $B_1, B_2$ are *conditionally independent given* $A$ if

$$\mathbb{P}(B_1 \cap B_2 \mid A) = \mathbb{P}(B_1 \mid A)\, \mathbb{P}(B_2 \mid A).$$

□

**Remark**

Conditional independence has **no** implications for independence, and vice versa. □

**Example (Counterexample: independent, but not conditionally independent)**

Consider $X_1, X_2$ two independent fair dice outcomes. $B_1 = \{X_1 = 3\}$, $B_2 = \{X_2 = 3\}$, $A = \{X_1 + X_2 = 6\}$.

$$\mathbb{P}(B_1 \mid A) = \frac{\mathbb{P}(B_1 \cap A)}{\mathbb{P}(A)} = \frac{1/36}{5/36} = \frac{1}{5}, \qquad \mathbb{P}(B_2 \mid A) = \frac{\mathbb{P}(B_2 \cap A)}{\mathbb{P}(A)} = \frac{1}{5},$$

$$\mathbb{P}(B_1 \cap B_2 \mid A) = \frac{\mathbb{P}(B_1 \cap B_2 \cap A)}{\mathbb{P}(A)} = \frac{1}{5}.$$

Hence they are independent but not conditionally independent given $A$. □

**Example (Counterexample: conditionally independent, but not independent)**


Let $X_1, X_2$ be samples without replacement from $[10]$. $B_1 = \{X_1 \text{ even}\}$, $B_2 = \{X_2 \text{ even}\}$, $A = \{X_1 \leq 6\} \cap \{X_2 \geq 7\}$.

Source manuscript page 21

$B_1$ and $B_2$ are not independent but conditionally independent given $A$. □

**Example (Counterexample: types of coins)**

With probability $\frac{9}{10}$ the coin is fair, with probability $\frac{1}{10}$ it is biased with $\mathbb{P}(\text{tail}) = 0.6$.




$B_1 = \{\text{first toss tails}\}$, $B_2 = \{\text{second toss tails}\}$, $A = \{\text{coin fair}\}$.

$$\mathbb{P}(B_1) = \mathbb{P}(B_1 \mid A)\,\mathbb{P}(A) + \mathbb{P}(B_1 \mid A^c)\,\mathbb{P}(A^c) = \tfrac{51}{100}, \qquad \mathbb{P}(B_2) = \tfrac{51}{100},$$

$$\begin{aligned}\mathbb{P}(B_1 \cap B_2) &= \mathbb{P}(B_1 \cap B_2 \mid A)\,\mathbb{P}(A) + \mathbb{P}(B_1 \cap B_2 \mid A^c)\,\mathbb{P}(A^c) \\ &= \tfrac{1}{4} \cdot \tfrac{9}{10} + \left(\tfrac{6}{10}\right)^2 \cdot \tfrac{1}{10} = \tfrac{261}{1000}.\end{aligned}$$

$B_1, B_2$ are clearly independent if the coin is fair, hence conditionally independent given $A$, but not independent by the computation above. □

# 7 Probability Distributions

## 7.1 Repeated Trials: Bernoulli and Binomial Distributions

**Definition**

We say a random variable $B$ is $\text{Ber}(p)$-distributed if $\mathbb{P}(B = 1) = p$, $\mathbb{P}(B = 0) = 1 - p$.

Source manuscript page 22

For all $n \in \mathbb{N}$, $p \in [0, 1]$, the *binomial distribution* $\text{Bin}(n, p)$ describes the number of successes among $n$ independent $\text{Ber}(p)$ trials. □

**Example (A biased coin with chance $p$ of head)**

Then $\Omega = \{0,1\}^n$, $|\Omega| = 2^n$, and for $\omega = (\omega_1, \dots, \omega_n) \in \Omega$,

$$\mathbb{P}(\omega) = p^{\#\{i\in[n]:\ \omega_i=1\}}(1-p)^{\#\{i\in[n]:\ \omega_i=0\}}.$$

Moreover, for the random variable $H : \Omega \to \mathbb{R}$, $\omega \mapsto \#\{i \in [n] :\ \omega_i = 1\} = \|\omega\|_1$,

$$\mathbb{P}(H=k) = \mathbb{P}\big(\{\omega\in\Omega :\ \|\omega\|_1 = k\}\big) = \sum_{\substack{\omega\in\Omega\\ \|\omega\|_1=k}} \mathbb{P}(\omega) = \binom{n}{k} p^k (1-p)^{n-k},$$

so $H$ is $\mathrm{Bin}(n,p)$-distributed by definition. □

**Definition**

If $X$ is any random variable such that $\mathbb{P}(X=k) = \binom{n}{k}p^k(1-p)^{n-k}$ for $k \in \{0,1,\dots,n\}$, then we say $X$ is $\mathrm{Bin}(n,p)$-distributed. □

## 7.2 Product Spaces and Infinitely Many Trials

**Note (-)**

The space $\Omega_i = \{0,1\}$ with $\mathbb{P}_i(0) = 1-p$ is the $\mathrm{Ber}(p)$ probability space, so the space we just described is

$$\Omega_n = \bigotimes_{i=1}^n \Omega_i, \qquad \mathbb{P}_n = \bigotimes_{i=1}^n \mathbb{P}_i \quad \text{(product measure)}.$$

Source manuscript page 23

In particular, restricting $\Omega_n$ and $\mathbb{P}_n$ to the first $n-1$ coordinates gives $\Omega_{n-1}, \mathbb{P}_{n-1}$. In fact, one can extend to

$$\Omega_\infty = \bigotimes_{i\geq 1} \Omega_i, \qquad \mathbb{P}_\infty = \bigotimes_{i\geq 1} \mathbb{P}_i,$$

which models an infinite sequence of independent $\mathrm{Ber}(p)$ trials, using the Kolmogorov extension theorem. We take as given that we can define a probability space $(\Omega, \mathcal{F}, \mathbb{P})$ on which it is possible to define an infinite sequence $(B_i)_{i\geq 1}$ of independent $\mathrm{Ber}(p)$-distributed random variables. □

**Observation**

For $n \geq 1$, $S := B_1 + \cdots + B_n$ is $\mathrm{Bin}(n,p)$-distributed.

*Proof.*

$$\mathbb{P}(S=k) = \mathbb{P}\big(\|(B_1,\dots,B_n)\|_1 = k\big) = \mathbb{P}\Big(\bigcup_{\substack{\omega\in\{0,1\}^n\\ \|\omega\|_1=k}} \{(B_1,\dots,B_n)=\omega\}\Big) = \sum_{\substack{\omega\in\{0,1\}^n\\ \|\omega\|_1=k}} \mathbb{P}(B_i = \omega_i\ \forall i)$$

$$\overset{\text{indep.}}{=} \sum_{\substack{\omega\in\{0,1\}^n\\ \|\omega\|_1=k}} \prod_{i=1}^n \mathbb{P}(B_i=\omega_i) = \sum_{\substack{\omega\in\{0,1\}^n\\ \|\omega\|_1=k}} p^k(1-p)^{n-k} = \binom{n}{k} p^k(1-p)^{n-k}.$$ □

## 7.3 Geometric and Negative Binomial Distributions

Source manuscript page 24

**Definition**

Say $G$ is Geom$(p)$-distributed if for $k \in \mathbb{N}$, $\mathbb{P}(G = k) = (1-p)^{k-1}p$. □

**Remark**

If $N := \inf\{k \geq 1 : \ B_k = 1\}$, then

$$\begin{aligned}\mathbb{P}(N = k) &= \mathbb{P}(B_1 = \cdots = B_{k-1} = 0, \ B_k = 1) \\ &= \mathbb{P}(B_1 = 0)\,\mathbb{P}(B_2 = 0)\cdots\mathbb{P}(B_{k-1} = 0)\,\mathbb{P}(B_k = 1) = (1-p)^{k-1}p.\end{aligned}$$

Hence $N$ is Geom$(p)$-distributed if the $B_i$ are all identically, independently Ber$(p)$-distributed. □

**Definition**

The *negative binomial distribution* NBin$(r,p)$ counts the number of Ber$(p)$ trials until $r$ successes. So Geom$(p)$ = NBin$(1,p)$. □

⋆ Exercise. If $X$ is NBin$(r,p)$-distributed, what is $\mathbb{P}(X = k)$ for $k \geq r$? Hint: $\mathbb{P}(X = r) = p^r$, $\mathbb{P}(X = r+1) = (1-p)\,p^r \cdot r$.

## 7.4 The Birthday Problem and the Rayleigh Distribution

Question. Assuming birthdays are uniformly distributed among 365 days, what is the probability of no collision among $k$ individuals?

$$\frac{365}{365}\cdot\frac{364}{365}\cdot\frac{363}{365}\cdots\frac{365-(k-1)}{365}. \qquad \text{? why not } \tfrac{}{365^k} \text{ ?}$$

Source manuscript page 25

Replacing 365 by $n$,

$$\mathbb{P}(\text{collision free among } k \text{ individuals}) = \prod_{i=1}^{k-1}\Big(1-\frac{i}{n}\Big).$$

Recall, for $\delta > 0$ small, $e^{-\delta} = 1 - \delta + O(\delta^2)$. For small $k \ll n$ and $i \leq k-1$, $1 - \frac{i}{n} \approx \exp(-\frac{i}{n})$, so

$$\mathbb{P}(\text{collision free among } k \text{ individuals}) \approx \prod_{i=1}^{k-1}\exp\Big(-\frac{i}{n}\Big) = \exp\Big(-\sum_{i=1}^{k-1}\frac{i}{n}\Big) = \exp\Big(-\frac{k(k-1)}{2n}\Big).$$

This becomes small when $k \approx \sqrt{n}$, $k = c\sqrt{n}$.

Fix $x > 0$ and let $X_n$ = number of samples until a repeat, when sampling uniformly at random with replacement from $[n]$. Then

$$\mathbb{P}\Big(\frac{X_n}{\sqrt{n}} > x\Big) = \prod_{i=1}^{\lceil x\sqrt{n}\rceil - 1}\Big(1-\frac{i}{n}\Big) \approx \exp\Big(-\frac{\lceil x\sqrt{n}\rceil(\lceil x\sqrt{n}\rceil - 1)}{2n}\Big) \longrightarrow \exp\Big(-\frac{x^2}{2}\Big) \quad \text{as } n \to \infty.$$

**Definition**

A random variable $X$ is *Rayleigh distributed* if $\mathbb{P}(X > x) = e^{-x^2/2}$ for $x \in \mathbb{R}_{\geq 0}$. □

## 7.5 Hypergeometric Distribution

$N$ balls, $m$ white, $k$ samples without replacement.

Source manuscript page 26

**Definition**

The $\mathrm{Hyp}(N, m, k)$ distribution is the distribution of the number of white balls drawn. If $N$ is hypergeometric $\mathrm{Hyp}(N, m, k)$-distributed, then

$$\mathbb{P}(N = j) = \frac{\binom{m}{j}\binom{N-m}{k-j}}{\binom{N}{k}}.$$

□

Note. If instead the sampling is with replacement, then

$$\mathbb{P}(N = j) = \binom{k}{j}\left(\frac{m}{N}\right)^j\left(1 - \frac{m}{N}\right)^{k-j} \sim \mathrm{Bin}\left(k, \frac{m}{N}\right).$$

# 8 Density and Distribution Functions

## 8.1 Probability Density Functions

Recall. For a discrete random variable $X$ with possible values $S = \{x \in \mathbb{R} : \mathbb{P}(X = x) > 0\}$, the probability mass function of $X$ is

$$p : S \longrightarrow \mathbb{R}, \qquad x \longmapsto \mathbb{P}(X = x).$$

Source manuscript page 27

Recall. $X$ is *discrete* if its set of possible values is countable, i.e., finite or countably infinite. $X$ is *continuous* if $\exists f : \mathbb{R} \to [0, \infty)$ such that $\forall a \leq b$,

$$\mathbb{P}(X \in [a, b]) = \int_a^b f\,dx.$$

If so,

$$\int_{-\infty}^{\infty} f(x)\,dx = \lim_{n\to\infty}\int_{-n}^{n} f(x)\,dx = \lim_{n\to\infty}\mathbb{P}(X \in [-n, n]) \overset{(*)}{=} 1.$$

Exercise. Formalize this $(*)$ using the definitions. In particular, notice $\mathbb{P}(X \in A) = \mathbb{P}(X^{-1}(A))$.

Notation. If $X$ follows a distribution $D$, we might write $X \sim D$.

**Definition**

For $X$ a continuous random variable, if $f : \mathbb{R} \to [0, \infty)$ is such that $\int_a^b f(x)\,dx = \mathbb{P}(X \in [a, b])$, then $f$ is called a *probability density function* for $X$. □

**Remark**

A random variable $X$ can have multiple pdfs, but all its pdfs are pairwise different on a null set, i.e., a set of Lebesgue measure 0. Equivalently, if $f, g$ are pdfs of $X$, then $\forall [a, b]$ we have $\int_a^b f(x)\,dx = \int_a^b g(x)\,dx$. We say in this case that $f = g$ *almost everywhere* (a.e.). □

## 8.2 Examples of Continuous Random Variables

Source manuscript page 28

**Example (Uniform on $[y, z]$)**

The only possible (identified mod null sets) pdf is

$$f(x) = \begin{cases} \dfrac{1}{z-y} & \text{if } x \in [y, z], \\ 0 & \text{otherwise.} \end{cases}$$

□

**Example (Wigner's semicircle law)**


Let $a > 0$. Then

$$f(x) = \begin{cases} \dfrac{2}{\pi a^2}\sqrt{a^2 - x^2}, & \text{if } |x| \le a, \\ 0, & \text{otherwise.} \end{cases}$$

□

**Example (Beta$(3, 3)$)**

$$f(x) = \begin{cases} 30\, x^2(1-x)^2, & 0 \le x \le 1, \\ 0, & \text{otherwise.} \end{cases}$$




For $a, b > 0$, $a, b \in \mathbb{N}$,

$$\text{Beta}(a, b): \qquad f(x) = \begin{cases} \dfrac{\Gamma(a+b)}{\Gamma(a)\,\Gamma(b)}\, x^{a-1}(1-x)^{b-1}, & 0 \le x \le 1, \\ 0, & \text{otherwise,} \end{cases}$$

gamma being the gamma function

$$\Gamma(r) := \int_0^\infty x^{r-1} e^{-x}\, dx.$$

□

**Proposition**

If $X$ has a continuous pdf $f$, then for $a \in \mathbb{R}$,

$$f(a) = \lim_{\varepsilon \downarrow 0^+} \frac{\mathbb{P}(X \in [a, a+\varepsilon])}{\varepsilon}.$$

Source manuscript page 29

*Proof.* Follows directly from the fundamental theorem of calculus and the definition of pdf. □

**Remark**

The converse holds, i.e., if $\exists X : \Omega \to \mathbb{R}$ a random variable such that

$$f(a) = \lim_{\varepsilon \downarrow 0} \frac{\mathbb{P}(X \in [a, a+\varepsilon])}{\varepsilon},$$

then $f$ is a pdf of $X$, and $X$ is a continuous random variable. □

**Example (Dart board)**

$R \to$ uniformly random point on the board. Board $= B(\vec{0}, 9)$. $D \to$ distance from $R$ to $\vec{0}$.
For $0 \le r < 9$, $0 < \varepsilon < 9 - r$,

$$\mathbb{P}(D \in [r, r+\varepsilon]) = \mathbb{P}\Big(R \in \overline{B(\vec{0}, r+\varepsilon)} \setminus \overline{B(\vec{0}, r)}\Big) = \frac{\pi(r+\varepsilon)^2 - \pi r^2}{81\pi} = \frac{2r\varepsilon + \varepsilon^2}{81}.$$

So

$$\lim_{\varepsilon \downarrow 0} \frac{1}{\varepsilon} \mathbb{P}(D \in [r, r+\varepsilon]) = \lim_{\varepsilon \downarrow 0} \frac{2r+\varepsilon}{81} = \frac{2r}{81} \qquad \text{for } 0 \le r < 9.$$

Therefore $D$ is continuous and has density

$$f(x) = \begin{cases} 2x/81, & 0 \le x < 9, \\ 0, & \text{otherwise.} \end{cases}$$

□

## 8.3 General Random Variables

Generally, a random variable need not be continuous or discrete.

Source manuscript page 30


**Definition**

For a random variable $X$, its *cumulative distribution function* is the function $F_X : \mathbb{R} \to [0, 1]$ given by

$$F_X(x) = \mathbb{P}(X \le x).$$

□


**Example ($\mathrm{Ber}(p)$)**



$$F(x) = \begin{cases} 0, & x < 0, \\ 1-p, & 0 \le x < 1, \\ 1, & x \ge 1. \end{cases}$$

□

**Example (Geom($p$))**





$$F(x) = \mathbb{P}(X \le x) = 1 - \mathbb{P}(X > x) = 1 - (1-p)^{\lfloor x \rfloor},$$

$$F(x) = \begin{cases} 0, & \text{if } x < 1, \\ 1-(1-p)^k & \text{for } k \le x < k+1,\ k \in \mathbb{N}. \end{cases}$$

□

**Example (Rayleigh)**

$$F_X(x) = \mathbb{P}(X \le x) = 1 - \mathbb{P}(X > x) = 1 - e^{-x^2/2}, \qquad x > 0.$$




□

Source manuscript page 31


**Example (Insurance deductible)**

\$500 deductible. Damage to car: $D \sim \text{Unif}[100, 1500]$. Cost to owner: $X = \min(D, 500)$.

$$\mathbb{P}(X \le x) = \mathbb{P}(\min(D, 500) \le x) = \begin{cases} \mathbb{P}(D \le x) & \text{if } x < 500, \\ 1, & x \ge 500. \end{cases}$$

For $100 \le x \le 500$, $\mathbb{P}(D \le x) = \mathbb{P}(D \in [100, x]) = \dfrac{x - 100}{1400}$.

$$\mathbb{P}(X \le x) = \begin{cases} 0, & x < 100, \\ \dfrac{x - 100}{1400}, & 100 \le x < 500, \\ 1, & x \ge 500. \end{cases}$$




□

## 8.4 Connection between cdf and pdf

For a continuous random variable $X$ with pdf $f$,

$$\begin{aligned} F(x) &= \mathbb{P}(X \le x) = \mathbb{P}(X \in (-\infty, x]) \\ &= \lim_{n\to\infty} \mathbb{P}(X \in [-n, x]) = \lim_{n\to\infty} \int_{-n}^{x} f(z)\,dz = \int_{-\infty}^{x} f(z)\,dz. \end{aligned}$$

Source manuscript page 32

Conversely, if $X$ has CDF $F$ that is continuous and $F'$ exists except at finitely many points, then

$$f(x) = \begin{cases} F'(x), & F \text{ differentiable at } x, \\ 0, & \text{otherwise} \end{cases}$$

is a pdf for $X$.

## 8.5 Connection between cdf and pmf

For a discrete random variable $X$ with possible values $S$ and pmf $p_X$,

$$F(x) = \mathbb{P}(X \le x) = \mathbb{P}\big(X \in S \cap (-\infty, x]\big) = \sum_{s \in S \cap (-\infty, x]} \mathbb{P}(X = s).$$

In particular, if $S$ has no accumulation (limit) points, then $F$ is piecewise constant.

Exercise. Conversely, if $X$ has cdf $F$, and $F$ is piecewise constant, then $X$ is discrete, and $S = \{x \in \mathbb{R} : F \text{ is discontinuous at } x\}$.

**Proposition (Read proof)**

$F : \mathbb{R} \to [0, 1]$ is a cdf $\iff$
① $F$ is nondecreasing;
② $F$ is right continuous, that is, $\lim_{\varepsilon \downarrow 0} F(x + \varepsilon) = F(x)\ \forall x \in \mathbb{R}$;
③ $\lim_{x\to-\infty} F(x) = 0$, $\lim_{x\to\infty} F(x) = 1$.

Source manuscript page 33

**Proposition**

If $(E_n)_{n\geq 1}$ are increasing events, then

$$\mathbb{P}\Big(\bigcup E_n\Big) = \lim_{n\to\infty} \mathbb{P}(E_n).$$

If $(F_n)_{n\geq 1}$ are decreasing events, then

$$\mathbb{P}\Big(\bigcap F_n\Big) = \lim_{n\to\infty} \mathbb{P}(F_n).$$

The proposition above is needed to prove the one on the previous page.

**Remark (Post-lecture)**

1. With the dart example, we worked out that a pdf for the distance to the center of the board was

$$f(x) = \begin{cases} \dfrac{2x}{81}, & 0 \leq x \leq 9, \\ 0, & \text{otherwise.} \end{cases}$$

   With this, we may compute for example

$$\mathbb{P}(1 \leq R \leq 2) = \int_1^2 \frac{2r}{81}\, dr = \frac{3}{81} = \frac{1}{27}.$$

2. If $X$ has cumulative distribution function $F$, then for any $a < b$, we have

$$\mathbb{P}(X \in (a,b]) = \mathbb{P}\big(\{X \leq b\} \setminus \{X \leq a\}\big) = \mathbb{P}(X \leq b) - \mathbb{P}(X \leq a) = F(b) - F(a).$$

□

# 9 Expectations

Source manuscript page 34

Expectations = means = averages: $\mathbb{E}X$.

**Example**

- Fair die roll $X$: $\frac{1}{6}\cdot 1 + \frac{1}{6}\cdot 2 + \cdots + \frac{1}{6}\cdot 6 = 3.5$.
- Unif$[0,1]$: $X \to \mathbb{E}X = \frac{1}{2}$.
- Unif$[y,z]$: $X \to \mathbb{E}X = \frac{y+z}{2}$.
- Semicircle, $f(x) = \frac{2}{\pi}\sqrt{1-x^2}$ for $-1 \leq x \leq 1$: $X \to \mathbb{E}X = 0$.

□

**Definition**

For a discrete random variable $X$, we set

$$\mathbb{E}X = \sum_{s\in S_X} s\cdot \mathbb{P}(X = s) = \sum_{s\in S_X} s\cdot p_X(s),$$

given the sum is finite or the infinite series is absolutely convergent. We require absolute convergence to avoid rearrangements affecting the value of the sum.
For a continuous random variable $Y$, we set

$$\mathbb{E}Y = \int_{\mathbb{R}} y\, f(y)\, dy,$$

the *expectation* of $Y$, given $\int_{\mathbb{R}} |y\, f(y)|\, dy < \infty$. □

**Example ($X \sim \mathrm{Bin}(n,p)$)**

$\mathbb{P}(X = k) = \binom{n}{k} p^k (1-p)^{n-k}$, $k \in [n] \cup \{0\}$.

$$\begin{aligned}\mathbb{E}X &= \sum_{k=0}^{n} k\, \mathbb{P}(X=k) = \sum_{k=0}^{n} k \binom{n}{k} p^k (1-p)^{n-k} \\ &= \sum_{k=0}^{n} k\, \frac{n!}{k!\,(n-k)!}\, p^k (1-p)^{n-k}\end{aligned}$$

Source manuscript page 35

$$\begin{aligned}&= np \sum_{k=1}^{n} \frac{(n-1)!}{(k-1)!\,(n-k)!}\, p^{k-1} (1-p)^{n-k} \\ &= np \sum_{j=0}^{n-1} \binom{n-1}{j} p^j (1-p)^{n-1-j} = np\big(p + (1-p)\big)^{n-1} = np.\end{aligned}$$

□


**Example ($G \sim \mathrm{Geom}(p)$)**

$\mathbb{P}(G = k) = p(1-p)^{k-1}$.

$$\begin{aligned}\mathbb{E}G &= \sum_{k\geq 1} k\, p(1-p)^{k-1} = p \sum_{k\geq 1} \sum_{j=1}^{k} (1-p)^{k-1} \\ &= p \sum_{j\geq 1} \sum_{k\geq j} (1-p)^{k-1} = p \sum_{j\geq 1} \frac{(1-p)^{j-1}}{p} = \frac{1}{p}.\end{aligned}$$

□

**Example (Dart board)**



$D$ = distance to center,

$$f_D(r) = \frac{2r}{r_0^2}, \qquad 0 \le r \le r_0.$$

$$\mathbb{E}D = \int_0^{r_0} r\, f_D(r)\, dr = \int_0^{r_0} \frac{2r^2}{r_0^2}\, dr = \frac{2}{3}\, r_0.$$

□

**Example (Non-example: St. Petersburg paradox)**

Casino setup: Pot initially contains \$1.

Source manuscript page 36

Player flips a coin: Heads = win pot; Tail = double value of the pot. $W \to$ winnings.

$$\mathbb{E}W = \sum_{k\ge 0} 2^k\, \mathbb{P}\big((k+1)\text{st toss is first head}\big) = \sum_{k\ge 0} 2^k\, \frac{1}{2^{k+1}} = \infty.$$

Two-player St. Petersburg. First player to flip heads wins $2^k$ from the other player, where $k = \#$ flips until heads. $Z =$ winnings / loss of player 1.

$$\mathbb{E}Z = \frac{1}{2}\cdot 2^1 - \frac{1}{2^2}\cdot 2^2 + \frac{1}{2^3}\cdot 2^3 - \cdots = 1 - 1 + 1 - 1 + 1 - 1 + \cdots$$

which does not converge. □

## 9.1 Change of Variables

**Example (Fair die roll $D$)**

$$D \le 3 \ \to\ \text{lose \$1}, \qquad D = 4 \ \to\ \text{win \$1}, \qquad D \ge 5 \ \to\ \text{win \$3}.$$

$W =$ winnings.

Source manuscript page 37

$$\mathbb{E}W = -1\cdot\tfrac{1}{6} - 1\cdot\tfrac{1}{6} - 1\cdot\tfrac{1}{6} + 1\cdot\tfrac{1}{6} + 3\cdot\tfrac{1}{6} + 3\cdot\tfrac{1}{6} = \tfrac{2}{3},$$
$$\mathbb{E}W = -1\cdot\tfrac{1}{2} + 1\cdot\tfrac{1}{6} + 3\cdot\tfrac{1}{3} = \tfrac{2}{3}.$$

With the second one, we view $W$ as a new random variable with its own probability mass function. □

**Proposition (In general)**

If $X : \Omega \to \mathbb{R}$ is discrete and $g : \mathbb{R} \to \mathbb{R}$,

$$\mathbb{E}(g(X)) = \sum_{s\in S_X} g(s)\cdot\mathbb{P}(X = s) = \sum_{y\in S_{g(X)}} y\cdot\mathbb{P}(g(X) = y),$$

given absolute convergence.

*Proof.* Exercise. Rearrange terms in the sum. □

**Proposition**

If $X$ is a random variable with pdf $f$, and $g : \mathbb{R} \to \mathbb{R}$, then provided absolute integrability,

$$\mathbb{E}(g(X)) = \int_{\mathbb{R}} g(x)\, f(x)\, dx.$$

*Proof (guidelines).* 1. Prove that if $X$ has density function $f$ with $f(x) = 0$, $x < 0$, then

$$\mathbb{E}X = \int_0^\infty \mathbb{P}(X > x)\, dx.$$

2. Prove with 1 that for $g : \mathbb{R} \to \mathbb{R}_{\geq 0}$,

Source manuscript page 38

$$\mathbb{E}g(X) = \int_0^\infty \mathbb{P}(g(X) > x)\, dx = \int_0^\infty \int_B f_X(y)\, dy\, dx, \qquad B = \{y \in \mathbb{R} \mid g(y) > x\}.$$

3. Change the order of integration via the Fubini–Tonelli theorem,

$$\mathbb{E}g(X) = \int_{\mathbb{R}} \int_0^{g(y)} dx\, f_X(y)\, dy = \int_{\mathbb{R}} g(y)\, f_X(y)\, dy.$$

4. Generalizing this to $g : \mathbb{R} \to \mathbb{R}$, apply what we proved to the positive and negative parts of $g$:

$$g_+(x) := \begin{cases} g(x), & \text{if } g(x) > 0, \\ 0, & \text{otherwise,} \end{cases} \qquad g_-(x) = \begin{cases} -g(x), & \text{if } g(x) < 0, \\ 0, & \text{otherwise.} \end{cases}$$

Then, by linearity of expectations,

$$\begin{aligned} \mathbb{E}g(X) &= \mathbb{E}g_+(X) - \mathbb{E}g_-(X) \\ &= \int_{\mathbb{R}} g_+(y)\, f_X(y)\, dy - \int_{\mathbb{R}} g_-(y)\, f_X(y)\, dy = \int_{\mathbb{R}} g(y)\, f_X(y)\, dy. \end{aligned}$$

□

Source manuscript page 39

**Example (Stick-breaking)**

$U \sim \mathrm{Unif}[0, \ell]$, $M = \max(U, \ell - U)$, $g(U) = \max(\ell - U, U)$.

$$\begin{aligned} \mathbb{E}M &= \int_0^\ell \max(x, \ell - x) \cdot f_U(x)\, dx \\ &= \int_0^\ell \max(x, \ell - x) \cdot \frac{1}{\ell}\, dx = 2 \int_{\ell/2}^\ell x \cdot \frac{1}{\ell}\, dx = \cdots \end{aligned}$$

□

Notation. Denote $\sum_{x \in S_X} |x|\, \mathbb{P}(X = x)$ by $\mathbb{E}|X|$, resp. $\int_{-\infty}^\infty |x|\, f_X(x)\, dx$ by $\mathbb{E}|X|$.

**Proposition (Linearity of expectation)**

① $\mathbb{E}(aX + b) = a\, \mathbb{E}X + b$, if $\mathbb{E}|X| < \infty$.
② Suppose $X, Y : \Omega \to \mathbb{R}$ are random variables with $\mathbb{E}|X|, \mathbb{E}|Y| < \infty$; then

$$\mathbb{E}(X + Y) = \mathbb{E}X + \mathbb{E}Y.$$

*Proof.* For continuous random variables these are properties of the Lebesgue integral. For discrete random variables, ① is trivial, ② follows by manipulating the definition and rewriting the sums (exercise). □

## 9.2 Moments

Source manuscript page 40

**Definition**

For a random variable $X$, the *nth moment of* $X$, denoted $m_n$, is $m_n := \mathbb{E}(X^n)$ whenever $X \geq 0$ or $\mathbb{E}(|X|^n) < \infty$. □

**Example ($U \sim \text{Unif}[0,1]$)**

$f_U(x) = 1$, $0 \leq x \leq 1$.

$$m_n = \mathbb{E}[U^n] = \int_0^1 x^n \, f_U(x)\, dx \quad \text{(change of variables)} \quad = \int_0^1 x^n \, dx = \frac{1}{n+1}.$$

□

**Example ($X \sim \text{Unif}[0,\ell]$)**

$f_X(x) = \dfrac{1}{\ell}$, $0 \leq x \leq \ell$. Then $X = \ell \cdot U$. By change of variables,

$$\mathbb{E}(X^n) = \mathbb{E}[(\ell U)^n] = \ell^n \, \mathbb{E}[U^n] = \frac{\ell^n}{n+1}.$$

□

**Fact**

If $X$ is bounded, i.e. $\text{Range}(X) \subseteq [-M, M]$ for some $M \geq 0$, then the raw moments $(m_n)_{n \in \mathbb{N}}$ determine the distribution of $X$.

If $X$ is not bounded, this is not true.

**Example (Counterexample)**

Let

$$\zeta(x) = \sum_{s \geq 1} \frac{1}{s^x}, \qquad x > 1,$$

be the Riemann zeta function. Define a random variable $X$ with

$$\mathbb{P}(X = k) = \frac{1}{\zeta(3)\, k^3}, \qquad k \geq 1.$$

Then

$$\mathbb{E}[X] = \sum_{k \geq 1} k \, \mathbb{P}(X = k) = \sum_{k \geq 1} \frac{1}{\zeta(3)} \cdot \frac{1}{k^2} = \frac{\zeta(2)}{\zeta(3)}, \qquad \mathbb{E}[X^n] = \sum_{k \geq 1} k^n \, \mathbb{P}(X = k) = \infty, \quad n > 1.$$

Source manuscript page 41

Define a random variable $Y$ such that why does such r.v. always exist?

$$\begin{aligned}\mathbb{P}(Y=0) &= \tfrac{1}{2}\,\mathbb{P}(X=1),\\ \mathbb{P}(Y=1) &= 0,\\ \mathbb{P}(Y=2) &= \mathbb{P}(X=2)+\tfrac{1}{2}\,\mathbb{P}(X=1),\\ \mathbb{P}(Y=k) &= \mathbb{P}(X=k) \quad \text{for } k\geq 3.\end{aligned}$$

Then $\mathbb{E}Y = \mathbb{E}X$, $\mathbb{E}(Y^n)=\infty$ for $n>1$, while they have different distributions. □

## 9.3 Medians and Quantiles

**Definition**

Given a random variable $X$, a *median* of $X$ is any value $a$ such that

$$\mathbb{P}(X\leq a)\geq \tfrac{1}{2} \quad \text{and} \quad \mathbb{P}(X\geq a)\geq \tfrac{1}{2}.$$

For $p\in[0,1]$, the *pth quantile* of $X$ is any value $a$ such that $\mathbb{P}(X\leq a)\geq p$ and $\mathbb{P}(X\geq a)\geq 1-p$. □

**Example (Dart board)**

Dart board of radius $r_0$, $D$ being the distance to the center. $\mathbb{P}(D\leq r)=r^2/r_0^2$, so a median for $D$ is $r$ such that $r^2/r_0^2=\frac{1}{2}$, so $r=r_0/\sqrt{2}$.
A $p$th quantile for $D$ is a value $r$ such that $r^2/r_0^2=p$, i.e. $r=r_0\sqrt{p}$. □

Source manuscript page 42

**Example ($U\sim \mathrm{Unif}\{1,2,3,\dots,6\}$)**

Any value $a\in[3,4]$ satisfies $\mathbb{P}(U\leq a)\geq\frac{1}{2}$, $\mathbb{P}(U\geq a)\geq\frac{1}{2}$. □

Exercise. $p$th quantile for $p\in(\frac{1}{3},\frac{1}{2})$ with $U$?

## 9.4 Variance

**Definition**

For a random variable $X$ with $\mathbb{E}X=\mu\in\mathbb{R}$, the *variance of* $X$ is

$$\mathrm{Var}(X) := \mathbb{E}\big[(X-\mu)^2\big]\leq\infty.$$

The *standard deviation* of $X$ is $\mathrm{SD}(X)=\sqrt{\mathrm{Var}(X)}=:\sigma$. □

**Remark**

By linearity of $\mathbb{E}$,

$$\mathrm{Var}(X)=\mathbb{E}\big[(X-\mu)^2\big]=\mathbb{E}[X^2]-2\mu\,\mathbb{E}X+\mu^2=\mathbb{E}[X^2]-\mathbb{E}[X]^2=m_2-m_1^2.$$

□

**Example ($X \sim \mathrm{Ber}(p)$)**

$$\mathrm{Var}(X) = \mathbb{E}[X^2] - \mathbb{E}[X]^2 = \mathbb{E}[X] - \mathbb{E}[X]^2 \quad (X = X^2 \text{ since } X = 0 \text{ or } 1) \quad = p - p^2.$$

□

**Example ($U \sim \mathrm{Unif}[a, b]$)**

$$\mathbb{E}[U^2] = \int_a^b x^2 \, \frac{1}{b-a} \, dx = \frac{b^2 + a^2 + ab}{3}, \qquad \mathbb{E}[U] = \frac{a+b}{2},$$


$$\mathrm{Var}(U) = \mathbb{E}[U^2] - \mathbb{E}[U]^2 = \frac{(b-a)^2}{12}.$$

□

Exercise. Come up with a distribution on $[a, b]$ with larger variance than the uniform one.

Source manuscript page 43

Hint.




All these distributions push data further from the mean / $\mathbb{E}$.

**Example ($\mathrm{Bin}(n, p)$)**

$$\begin{aligned}
\mathbb{E}[X^2] &= \sum_{k=0}^{n} k^2 \, \mathbb{P}(X = k) = np \sum_{k=1}^{n} k \, \frac{(n-1)!}{(k-1)!\,(n-k)!} \, p^{k-1}(1-p)^{n-k} \\
&= np \sum_{k=1}^{n} k \, \mathbb{P}\big(\mathrm{Bin}(n-1, p) = k-1\big) \\
&= np \sum_{k=0}^{n-1} (k+1) \, \mathbb{P}\big(\mathrm{Bin}(n-1, p) = k\big) \\
&= np\Big( \sum k \, \mathbb{P}\big(\mathrm{Bin}(n-1, p) = k\big) + \sum \mathbb{P}\big(\mathrm{Bin}(n-1, p) = k\big) \Big) \\
&= np\big((n-1)p + 1\big) = n^2p^2 - np^2 + np.
\end{aligned}$$

$[\mathbb{E}X]^2 = (np)^2$, so

$$\mathbb{E}[X^2] - (\mathbb{E}X)^2 = np(1-p) = \mathrm{Var}(X).$$

Recall we can view $\mathrm{Bin}(n, p)$ as the sum of $n$ independent Bernoulli distributions, and we observe linearity in variance here:

$$\mathrm{Var}\left(\mathrm{Bin}(n, p)\right) = n \ \mathrm{Var}\left(\mathrm{Ber}(p)\right).$$

Source manuscript page 44

In general, linearity holds for (mutually) independent random variables only. □

**Proposition**

For a random variable $X$ and $a, b \in \mathbb{R}$,

$$\mathbb{E}[aX + b] = a\,\mathbb{E}X + b, \qquad \mathrm{Var}(aX + b) = a^2\ \mathrm{Var}(X).$$

*Proof.* We have discussed the linearity of expectation. Variance follows from it:

$$\begin{aligned}\mathrm{Var}(aX+b) &:= \mathbb{E}\Big\{\big[(aX+b) - \mathbb{E}(aX+b)\big]^2\Big\} = \mathbb{E}\Big\{\big[aX + b - a\,\mathbb{E}X - b\big]^2\Big\} \\ &= \mathbb{E}\big[(aX - a\,\mathbb{E}X)^2\big] = a^2\,\mathbb{E}\big[(X - \mathbb{E}X)^2\big] = a^2\ \mathrm{Var}(X).\end{aligned}$$

□

**Proposition**

$\mathrm{Var}(X) = 0 \iff X$ is *degenerate*, i.e., $\exists a \in \mathbb{R}$ such that $\mathbb{P}(X = a) = 1$.

*Proof.* ($\Leftarrow$)

$$\mathrm{Var}(X) = \mathbb{E}\big[(X - \mathbb{E}X)^2\big] = \mathbb{E}\big[(X - a)^2\big] = \mathbb{E}[X^2] - a^2 = a^2 \cdot \mathbb{P}(X = a) - a^2 = a^2 \cdot 1 - a^2 = 0.$$

($\Rightarrow$) For the discrete case, note that

$$\mathrm{Var}(X) = 0 = \sum_{x \in S_X} (x - \mu)^2\,\mathbb{P}(X = x) \iff x = \mu,\ \forall x \in S_X.$$

Source manuscript page 45

Thus $X$ is degenerate by $a = \mu$: $\mathbb{P}(X = \mu) = 1$.

For the continuous case, $\mathrm{Var}(X) > 0$ in fact, and $X$ cannot be degenerate: first notice $\int_{\{c\}} f\,d\lambda = 0$, $\forall c \in \mathbb{R}$, since the singleton set $\{c\}$ has Lebesgue measure 0. Hence by definition, $\mathbb{P}(X = c) = \int_{\{c\}} f\,d\lambda = 0$.

Consider $\mathbb{P}(|X - \mu| < \varepsilon)$ for $\varepsilon > 0$. Then ranging $\varepsilon$ over $\frac{1}{n}$, by continuity of measure, $\mathbb{P}(|X - \mu| < \varepsilon) \to \mathbb{P}(X = \mu) = 0$ as $\varepsilon \downarrow 0$. Pick $\varepsilon > 0$ such that $\mathbb{P}(|X - \mu| < \varepsilon) \le \frac{1}{2}$, hence $\mathbb{P}(|X - \mu| \ge \varepsilon) \ge \frac{1}{2}$, and

$$\begin{aligned}\mathrm{Var}(X) &= \int_{\mathbb{R}} (x-\mu)^2 f(x)\,dx \ \ge \int_{|x-\mu|\ge\varepsilon} (x-\mu)^2 f(x)\,dx \ \ge\ \varepsilon^2 \int_{|x-\mu|\ge\varepsilon} f(x)\,dx \\ &= \varepsilon^2\,\mathbb{P}(|X-\mu| \ge \varepsilon) \ \ge\ \frac{\varepsilon^2}{2} > 0.\end{aligned}$$

□

# 10 The Normal / Gaussian Distribution

Source manuscript page 46

**Definition**

A random variable $X$ has the *standard Gaussian distribution* if it is continuous and has pdf

$$\varphi(x) = \frac{1}{\sqrt{2\pi}}\, e^{-\frac{x^2}{2}}.$$


□

**Remark**

We can then verify that

- $\int_{\mathbb{R}} \varphi(x)\,dx = 1$;

- $\mathbb{E}X = \int_{\mathbb{R}} x\,\varphi(x)\,dx = 0.$




Indeed, define

$$\varphi(x)\varphi(y) =: g(x,y) = \frac{1}{2\pi}\, e^{-\frac{x^2+y^2}{2}},$$

which can be viewed as generated by $\varphi(x)$ rotating along the $z$-axis, since for every $(x,y)$ such that $x^2+y^2=r^2$, $g$ takes the same value. Thus we can compute

$$\int_{\mathbb{R}}\int_{\mathbb{R}} g(x,y)\,dx\,dy = \int_{\mathbb{R}}\int_{\mathbb{R}} \varphi(x)\varphi(y)\,dx\,dy = \int_{\mathbb{R}} \varphi(x)\,dx \int_{\mathbb{R}} \varphi(y)\,dy = \Big[\int_{\mathbb{R}} \varphi(x)\,dx\Big]^2$$

(by Fubini's theorem), by applying the shell method, viewing the solid generated by revolution of

$$[0,\infty) \to \mathbb{R}, \qquad r \mapsto \frac{1}{2\pi}\, e^{-\frac{r^2}{2}}$$

around the $z$-axis:

Source manuscript page 47

$$\begin{aligned}\int_{\mathbb{R}}\int_{\mathbb{R}} g(x,y)\,dx\,dy &= \int_0^\infty 2\pi r\cdot\frac{1}{2\pi}\, e^{-\frac{r^2}{2}}\,dr = \int_0^\infty r\, e^{-r^2/2}\,dr = \int_0^\infty e^{-x}\,dx = \int_0^{-\infty} e^{u}\,(-du)\\ &= \int_{-\infty}^0 e^u\,du = e^0 - e^{-\infty} = 1.\end{aligned}$$

Thus $\big(\int_{\mathbb{R}}\varphi(x)\,dx\big)^2 = 1,\ \varphi(x)\ge 0 \implies \int_{\mathbb{R}}\varphi(x)\,dx = 1.$ □

**Fact**

If $X$ is standard Gaussian, then $\mathbb{E}[X^2] = 1$.

*Proof.*

$$\begin{aligned}\mathbb{E}[X^2] &= \int_{\mathbb{R}} x^2\varphi(x)\,dx = \int_{\mathbb{R}} \frac{x^2\, e^{-\frac{x^2}{2}}}{\sqrt{2\pi}}\,dx \qquad \big(u = x,\ dv = x\, e^{-\frac{x^2}{2}}\,dx\big)\\ &= \frac{1}{\sqrt{2\pi}}\Big[\big(-x\, e^{-\frac{x^2}{2}}\big)\Big|_{-\infty}^{\infty} + \int_{\mathbb{R}} e^{-\frac{x^2}{2}}\,dx\Big] = \frac{1}{\sqrt{2\pi}}\big[0 - 0 + \sqrt{2\pi}\big] = 1.\end{aligned}$$

□

Since $\mathbb{E}X = 0$, it implies

$$\mathrm{Var}(X) = \mathbb{E}(X^2) - (\mathbb{E}X)^2 = 1 - 0^2 = 1.$$

**Definition**

The standard Gaussian distribution is also called the *standard normal distribution*, denoted by

$$\mathcal{N}\big(\mu = 0, \underbrace{\sigma^2}_{\text{variance}} = 1\big), \qquad \text{short as } \mathcal{N}(0,1).$$

If $X \sim \mathcal{N}(0,1)$, then for $\mu \in \mathbb{R}$, $\sigma > 0$, the random variable $\sigma X + \mu$ is $\mathcal{N}(\mu, \sigma^2)$-*distributed*. □

Source manuscript page 48

**Proposition**

Suppose $Y = \sigma X + \mu$ is $\mathcal{N}(\mu, \sigma^2)$-distributed, i.e. $X \sim \mathcal{N}(0,1)$. Then

$$\mathbb{E}[\sigma X + \mu] = \sigma\, \mathbb{E}X + \mu = \mu, \qquad \text{and} \qquad \operatorname{Var}[\sigma X + \mu] = \sigma^2 \operatorname{Var}(X) = \sigma^2.$$

**Definition**

The *cumulative distribution function* of the Gaussian distribution is denoted

$$\Phi(x) := \int_{-\infty}^{x} \frac{1}{\sqrt{2\pi}}\, e^{-s^2/2}\, ds.$$

□

**Proposition**

Furthermore, if $Y$ is $\mathcal{N}(\mu, \sigma^2)$-distributed, then $Y$ has CDF

$$F(y) = \mathbb{P}(Y \le y) = \mathbb{P}(\sigma X + \mu \le y) = \mathbb{P}\Big(X \le \frac{y-\mu}{\sigma}\Big) = \Phi\Big(\frac{y-\mu}{\sigma}\Big)$$

and ("a") pdf

$$f(y) = F'(y) = \frac{d\,\Phi\big(\frac{y-\mu}{\sigma}\big)}{dy} = \frac{1}{\sigma}\,\varphi\Big(\frac{y-\mu}{\sigma}\Big) = \frac{1}{\sqrt{2\pi\sigma^2}} \exp\Big(-\frac{(y-\mu)^2}{2\sigma^2}\Big).$$

If $Y \sim \mathcal{N}(\mu, \sigma^2)$, then for $[a,b] \subseteq \mathbb{R}$,

$$\mathbb{P}(a \le Y \le b) = \mathbb{P}(a \le \sigma X + \mu \le b) = \mathbb{P}\Big(\frac{a-\mu}{\sigma} \le X \le \frac{b-\mu}{\sigma}\Big).$$

In particular,

$$\mathbb{P}(|Y - \mu| \le k\sigma) = \mathbb{P}(|X| \le k)$$

Source manuscript page 49

$$= \int_{-k}^{k} \frac{1}{\sqrt{2\pi}}\, e^{-x^2/2}\, dx = \Phi(k) - \Phi(-k).$$

$$\begin{aligned} \text{For } k = 1, &\quad \Phi(1) - \Phi(-1) = 0.6826, \\ k = 2, &\quad \Phi(2) - \Phi(-2) = 0.95, \\ k = 3, &\quad \Phi(3) - \Phi(-3) = 0.997, \\ k = 5, &\quad \Phi(5) - \Phi(-5) = 1 - \frac{5.7}{10^7}. \end{aligned}$$

These are known as the *empirical rules*.

**End of Midterm 1 Material**

# 11 Selected Problems and Tricks

Worked problems from Homework 1–2 (Anderson–Seppäläinen–Valkó) and Midterm 1, kept here for the *reusable tricks* they carry. Each ends with the trick stated on its own, in the form it will be needed again.

## 11.1 Hidden Conditioning: the Twins Problem

**Example (Homework 1 — twins)**

Miranda is expecting twins. A third of twin births are identical twins (always the same sex, that common sex being a fair coin flip); the other two thirds are fraternal twins (two independent fair sexes). (a) What is $\mathbb{P}(\text{both girls})$? (b) Given that both are girls, what is $\mathbb{P}(\text{identical})$?

Solution. The sample space must carry the hidden type: one outcome is a pair $(\text{type}, \text{sexes})$, with masses assigned by the multiplication rule $\mathbb{P}(\text{type})\,\mathbb{P}(\text{sexes} \mid \text{type})$:

$$\mathbb{P}(\text{Id}, GG) = \mathbb{P}(\text{Id}, BB) = \tfrac{1}{3}\cdot\tfrac{1}{2} = \tfrac{1}{6}, \qquad \mathbb{P}(\text{Fr}, **) = \tfrac{2}{3}\cdot\tfrac{1}{4} = \tfrac{1}{6} \quad \text{for each of } GG, GB, BG, BB.$$

Six atoms of mass $\frac{1}{6}$: the problem is secretly a fair die. Then

$$\text{(a)}\quad \mathbb{P}(GG) = \mathbb{P}(\text{Id}, GG) + \mathbb{P}(\text{Fr}, GG) = \tfrac{1}{6} + \tfrac{1}{6} = \tfrac{1}{3}, \qquad \text{(b)}\quad \mathbb{P}(\text{Id} \mid GG) = \frac{1/6}{1/3} = \frac{1}{2}.$$

□

**Remark (Trick: model the hidden type)**

The tempting answer $\mathbb{P}(GG) = \frac{1}{4}$ assumes the two sexes are independent fair coins — but the premise contradicts this: an identical pair is *one* coin flip copied twice, so same-sex outcomes are inflated ($\mathbb{P}(GG) = \mathbb{P}(BB) = \frac{1}{3}$, $\mathbb{P}(GB) = \mathbb{P}(BG) = \frac{1}{6}$). Whenever a problem mixes types (which coin, which bin, which kind of twin), one outcome of $\Omega$ is a complete history *including the type*; probabilities of the visible event are then reassembled by total probability, and conditioning is "cross out the atoms outside $B$, renormalize by $\mathbb{P}(B)$". Seeing same-sex evidence *does* carry information about the type: $\mathbb{P}(\text{Id} \mid GG) = \frac{1}{2} > \frac{1}{3}$. □

## 11.2 The $k$-Selection Problem

**Example (Homework 2 — ASV 2.82, the secretary problem)**

$N$ candidates arrive one by one in uniformly random order. Strategy: let the first $k$ pass, then hire the first candidate better than everyone seen so far (if none, hire the last). Let $A = \{\text{best candidate hired}\}$. (a) Compute $\mathbb{P}(A)$. (b) Which $k$ is optimal? (c) Find $\lim_{N\to\infty} k^*/N$.

Solution. (a) Condition on the position $B$ of the best candidate; $\mathbb{P}(B = i) = \frac{1}{N}$. For $i \le k$ the best walks away. For $i > k$, the best is hired iff no one in positions $k+1, \dots, i-1$ triggers a hire, which happens iff the best of the first $i-1$ candidates sits among the first $k$ positions; given $B = i$ the remaining relative

order is uniform, so this leader is uniform over $i-1$ slots:

$$\mathbb{P}(A \mid B=i)=\frac{k}{i-1} \qquad \Longrightarrow \qquad P_k := \mathbb{P}(A)=\frac{k}{N}\sum_{j=k}^{N-1}\frac{1}{j} \quad (k\geq 1), \qquad P_0=\tfrac{1}{N}.$$

(b) Compare consecutive values (the *discrete derivative*):

$$P_{k+1}-P_k=\frac{1}{N}\Big(\sum_{j=k+1}^{N-1}\frac{1}{j}-1\Big).$$

The tail is strictly decreasing in $k$, so $(P_k)$ increases then decreases (unimodal), and

$$k^*=\min\Big\{k\geq 1:\ \sum_{j=k+1}^{N-1}\frac{1}{j}\leq 1\Big\}.$$

(c) Sandwiching the harmonic tail between integrals, $\ln\frac{N}{k^*+1}\leq 1<\ln\frac{N-1}{k^*-1}$, i.e. $\frac{N}{e}-1\leq k^*<\frac{N-1}{e}+1$; dividing by $N$,

$$\frac{k^*}{N}\longrightarrow\frac{1}{e}\approx 0.368, \qquad \text{and in fact } P_{k^*}\longrightarrow\frac{1}{e} \text{ as well.}$$

□

**Remark (Trick: the discrete derivative test)**

To maximize a sequence over $k\in\mathbb{Z}$, the analogue of solving $f'=0$ is studying the sign of $\Delta f(k)=f(k+1)-f(k)$; "$f'$ changes sign once" becomes unimodality, and the maximizer is the threshold index. The same move finds the mode of $\mathrm{Bin}(n,p)$ via the ratio $\mathbb{P}(X=k+1)/\mathbb{P}(X=k)$. Division of labour: *integral comparison* locates the maximum only up to $O(\sqrt{N})$ (the top is flat — neighbouring $P_k$ differ by $O(1/N^2)$ while the integral bounds carry $O(1/N)$ slack), so integrals give the asymptotics (c), differences give the exact answer (b). Heuristic first, on scratch paper: maximizing $x\ln(1/x)$ gives $x=1/e$, telling you what to aim for. □

## 11.3 Von Neumann's Trick: a Fair Coin from a Biased One

**Example (Homework 2 — ASV 2.88)**

A coin has unknown $\mathbb{P}(H)=p\in(0,1)$. Use it to produce a fair coin.

Solution. Flip twice per round; rounds independent. Within a round,

$$\mathbb{P}(HT)=p(1-p)=\mathbb{P}(TH), \qquad \mathbb{P}(HH)=p^2, \qquad \mathbb{P}(TT)=(1-p)^2.$$

Declare HEADS on $HT$, TAILS on $TH$; on $HH$ or $TT$ discard the round and repeat.
Termination. A round is decisive with probability $r=2p(1-p)>0$, so $\mathbb{P}(\text{still running after } m \text{ rounds})=(1-r)^m\to 0$: the procedure stops with probability 1 (the run-forever event is nonempty but null — compare the single point on the dart board).
Fairness. Partition by the first decisive round:

$$\mathbb{P}(\text{HEADS})=\sum_{m\geq 1}(1-r)^{m-1}\,p(1-p)=\frac{p(1-p)}{2p(1-p)}=\frac{1}{2},$$

and identically for TAILS. Equivalently: conditioned on a round being decisive, $HT$ and $TH$ are equally likely. The number of rounds is $\mathrm{Geom}(2p(1-p))$, so the expected number of flips is $\frac{1}{p(1-p)}$ (minimal, 4, at $p=\frac{1}{2}$). □

**Remark (Trick: symmetrize so the unknown cancels)**

$HT$ and $TH$ have the same probability *whatever* $p$ *is* — the construction manufactures a symmetry instead of estimating $p$. Two standing sub-patterns: (i) *partition by the first decisive round* (geometric masses summing cleanly — also behind the dice game of §3.1 and the parity computation below); (ii) conditional fairness transfers to unconditional fairness only because the conditioning event has probability one, so the termination half of the argument is load-bearing, not decoration. □

## 11.4 The Indicator Trick

**Example (Homework 2 — ASV 3.78, expected matches)**

In the Hats example of §3.2 ($n$ people, uniformly permuted hats), find the expected number of people who receive their own hat.

Solution. Let $E_i = \{\text{person } i \text{ gets their own hat}\}$ and

$$X = \sum_{i=1}^{n} \mathbf{1}_{E_i}, \qquad \mathbb{P}(E_i) = \frac{(n-1)!}{n!} = \frac{1}{n}, \qquad \mathbb{E}[\mathbf{1}_{E_i}] = \mathbb{P}(E_i).$$

By linearity of expectation,

$$\mathbb{E}[X] = \sum_{i=1}^{n} \mathbb{P}(E_i) = n \cdot \frac{1}{n} = 1 \qquad \text{for every } n.$$

□

**Remark (Trick: unions care about overlap, expectations do not)**

The $E_i$ are neither disjoint nor independent ($\mathbb{P}(E_iE_j) = \frac{1}{n(n-1)} \neq \frac{1}{n^2}$) — and linearity does not care. The apparent double-counting is exactly what $X$ measures: a permutation fixing 3 people contributes 3. Contrast with §3.2, where the *probability of the union* $\mathbb{P}(\bigcup E_i) \approx 1 - e^{-1}$ required full inclusion–exclusion. Write the count as a sum of indicators whenever only an expectation is asked; reach for inclusion–exclusion only when a union is asked. □

## 11.5 A Biased Coin from a Fair One: Binary Expansions

**Example (Midterm 1 — the converse of von Neumann)**

Given a fair coin and any $p \in (0,1)$ (possibly irrational), produce a Ber($p$) outcome.

Solution. Write $p = 0.p_1p_2p_3\ldots$ in binary. Flip the fair coin to produce independent bits $B_1, B_2, \ldots$, and let $N = \min\{i : B_i \neq p_i\}$ be the first disagreement. Output *success* if $B_N = 0$ (and $p_N = 1$), *failure* if $B_N = 1$.
Termination. Each flip matches $p$'s bit with probability $\frac{1}{2}$ regardless of the bit, so $N \sim \text{Geom}(\frac{1}{2})$: finite almost surely, two flips expected.
Correctness. Success at step $i$ means $B_1 = p_1, \ldots, B_{i-1} = p_{i-1}$, $B_i = 0 < p_i = 1$ — disjoint events, one for each $i$ with $p_i = 1$, of probability $2^{-i}$. Hence

$$\mathbb{P}(\text{success}) = \sum_{i:\, p_i = 1} 2^{-i} = p.$$

□

**Remark (Trick: realize a number as a disjoint union of events)**

The bits define $U = \sum_{i\geq 1} B_i 2^{-i} \sim \mathrm{Unif}[0,1]$, and the procedure outputs $\mathbf{1}_{\{U<p\}}$: the comparison $U < p$ is decided at the first disagreeing bit (lexicographic order), so finitely many flips suffice almost surely; the tie $\{U = p\}$ needs every bit to agree and has probability $\lim_n 2^{-n} = 0$ by continuity of probability. The reusable move runs *backwards* from the usual one: given a series you want to equal a probability (here the expansion of $p$), hunt for disjoint events carrying exactly those masses — indexed, as usual, by a first decisive time. □

## 11.6 The Tail-Sum Formula

**Proposition (tail-sum formula)**

If $X$ takes values in $\{0, 1, 2, \dots\}$, then

$$\mathbb{E}[X] = \sum_{k\geq 1} \mathbb{P}(X \geq k).$$

Continuous twin, for $X \geq 0$ (used in step 1 of the change-of-variables proof, §9.1):

$$\mathbb{E}[X] = \int_0^\infty \mathbb{P}(X > x)\, dx.$$

*Proof.* All terms are nonnegative, so the double sum may be reordered:

$$\mathbb{E}[X] = \sum_{k\geq 1} k\,\mathbb{P}(X = k) = \sum_{k\geq 1}\sum_{j=1}^{k} \mathbb{P}(X = k) = \sum_{j\geq 1}\sum_{k\geq j} \mathbb{P}(X = k) = \sum_{j\geq 1} \mathbb{P}(X \geq j).$$ □

**Example (minimum and maximum of two dice)**

Roll two fair dice independently; let $m$ be the minimum and $M$ the maximum. Tails of minima factor:

$$\mathbb{P}(m \geq k) = \mathbb{P}(\text{both} \geq k) = \left(\frac{7-k}{6}\right)^2 \implies \mathbb{E}[m] = \sum_{k=1}^{6} \left(\frac{7-k}{6}\right)^2 = \frac{36+25+16+9+4+1}{36} = \frac{91}{36}.$$

And since $m + M = D_1 + D_2$, linearity gives $\mathbb{E}[M] = 7 - \frac{91}{36} = \frac{161}{36}$ — no new sums. □

**Remark (Trick: compute through tails)**

Use the tail-sum when the tail is simpler than the pmf — which is automatic for minima ($\mathbb{P}(\min > k)$ factors over independent coordinates) and for geometrics ($\mathbb{P}(G > k) = (1-p)^k$; this is how $\mathbb{E}[\mathrm{Geom}(p)] = \sum_{k\geq 0}(1-p)^k = \frac{1}{p}$ in one line). Same principle continuously: for $U_1, \dots, U_n$ iid $\mathrm{Unif}[0,1]$, $\mathbb{P}(\min > x) = (1-x)^n$ gives $\mathbb{E}[\min] = \int_0^1 (1-x)^n\, dx = \frac{1}{n+1}$, while $\mathbb{P}(\max \leq x) = x^n$ gives the density $nx^{n-1}$ and $\mathbb{E}[\max] = \frac{n}{n+1}$. □

## 11.7 First-Step Analysis

**Example (gambler's ruin, fair game)**

Anna and Boris bet \$1 on independent fair flips until one of them is broke; the total capital is $N$ and Anna currently holds $i$. What is the probability $p_i$ that Anna ends with everything?

Solution. Condition on the next flip (law of total probability): for $0 < i < N$,

$$p_i = \tfrac{1}{2}\, p_{i-1} + \tfrac{1}{2}\, p_{i+1}, \qquad p_0 = 0,\ p_N = 1.$$

The recursion says $p_{i+1} - p_i = p_i - p_{i-1}$: the increments are constant, so $p_i$ is linear in $i$, and the boundary values force

$$p_i = \frac{i}{N}.$$

(Smallest case, $N = 3$: $p_1 = \frac{1}{2}p_2$ and $p_2 = \frac{1}{2}p_1 + \frac{1}{2}$ give $p_1 = \frac{1}{3}$, $p_2 = \frac{2}{3}$.) □

**Remark (Trick: condition on the first step)**

When a random process *restarts* after one step, conditioning on that step converts an unknown probability into a system of linear equations — no series needed. The dice game of §3.1 yields to the same move: $a = \mathbb{P}(A \text{ wins})$ satisfies $a = \frac{1}{3} + \frac{2}{3} \cdot \frac{1}{3}\, a$ (A wins now, or both miss and the game restarts), giving $a = \frac{3}{7}$ without summing the geometric series. □

## 11.8 Parity via Generating Functions

**Example (Homework 2, bonus — $\mathbb{P}(\mathrm{Bin}(n,p)$ is even))**

With $q = 1 - p$, the binomial theorem evaluated at $q + p$ and $q - p$ gives

$$1 = (q+p)^n = \sum_{k=0}^{n} \binom{n}{k} p^k q^{n-k}, \qquad (1-2p)^n = (q-p)^n = \sum_{k=0}^{n} (-1)^k \binom{n}{k} p^k q^{n-k}.$$

Adding kills the odd terms and doubles the even ones:

$$\mathbb{P}(X \text{ even}) = \frac{1 + (1-2p)^n}{2}.$$

Sanity: $p = \frac{1}{2}$ gives $\frac{1}{2}$ for all $n \geq 1$; $n = 1$ gives $1 - p$. □

**Remark (Trick: evaluate at $\pm 1$ to filter a parity)**

Plugging $\pm$ the success weight into the expansion and averaging extracts every second term. The same filtering works by partitioning into consecutive pairs: for $N \sim \mathrm{Geom}(p)$, pairing $\{1,2\}, \{3,4\}, \ldots$ (or summing the even-index geometric series) gives $\mathbb{P}(N \text{ even}) = \frac{1-p}{2-p} < \frac{1}{2}$ — odd indices always carry more mass, since each even index is reached only by surviving the odd one before it. □